

GENERAL NOTES FOR ACCESS :

(TO COMPLY WITH SECTIONS AS 1228.1-2009 & PART D3 OF THE BCA)

SECTION 6.6 VISUAL INDICATORS ON GLAZING

WHERE THERE IS NO HANDRAIL OR TRANSOM ALL FULLY GLAZED DOORS, Sidelights INCLUDING GLAZING CAPABLE OF BEING MISTAKEN FOR A DOORWAY SHALL BE CLEARLY MARKED THE FULL WIDTH WITH A SOLID CONTRASTING LINE, THE CONTRASTING LINE SHALL BE NOT LESS THAN 75mm WIDE AND SHALL EXTEND ACROSS THE FULL WIDTH OF THE GLAZING, THE LOWER EDGE SHALL BE BETWEEN 900mm & 1000mm ABOVE FLOOR LEVEL. CONTRASTING LINE ON GLAZING SHALL HAVE A 30% LUMINANCE CONTRAST WHEN VIEWED AGAINST THE FLOOR SURFACE.

SECTION 7 FLOOR OR GROUND SURFACES ON CONTINUOUS ACCESSIBLE PATHS OF TRAVEL

FLOOR SHALL HAVE A SLIP RESISTANT SURFACE WITH A MAX 5mm VARIATION IN SURFACE, CARPET OR ANY SOFT FLEXIBLE MATERIAL ON THE FLOOR SURFACE SHALL HAVE A PILE HEIGHT OF THICKNESS OF MAX OF 11mm AND CARPET BACKING SHALL BE A MAX OF 4mm IN THICKNESS, EXPOSED EDGES OF FLOOR COVERINGS SHALL HAVE A TRIM FASTENED TO THE FLOOR THE ENTIRE LENGTH OF THE EXPOSED EDGE.

SECTION 8 BRAILLE & TACTILE SIGNS

BRAILLE AND TACTILES SIGNAGE TO BE PROVIDED FOR SANITARY FACILITIES SIGNS MUST BE NOT LESS THAN 1200mm AND NOT HIGHER THAN 1600mm ABOVE THE FLOOR SURFACE. SIGNS IDENTIFYING ROOMS MUST BE LOCATED ON THE WALL ON THE LATCH SIDE OF THE DOOR WITH THE LEADING EDGE OF THE SIGN LOCATED BETWEEN 50mm AND 300mm OR ARCHITRAVE OR WHERE NOT POSSIBLE THE SIGN MAY BE PLACED ON THE DOOR, DOORWAYS & DOOR NOTES (TO COMPLY WITH SECTIONS 13 AS 1428.1-2009 & PART D2.19 OF THE BCA)

- ALL EXIT DOORS TO SWING IN DIRECTION OF EGRESS.
- ALL DOORWAYS SHALL HAVE A MIN LUMINANCE CONTRAST OF 30% BETWEEN DOOR SYSTEM COMPONENTS AND WALLS.
- DOORWAYS ON A CONTINUOUS PATH OF TRAVEL SHALL HAVE A 650mm CLEAR OPENING.
- DOORS THAT FORM A CONTINUOUS PATH OF TRAVEL MUST BE OPENABLE WITHOUT A KEY FROM THE SIDE THAT FACES A PERSON SEEKING EGRESS BY A SINGLE HAND DOWNWARD ACTION.
- DOOR HANDLES TO BE BETWEEN 900mm AND 1100mm FROM THE FLOOR.
- CLEARANCE BETWEEN THE DOOR HAND AND DOOR FACE SHALL BE 35mm & 45mm.

DISABLED TOILET NOTES:

(TO COMPLY WITH SECTIONS 13 AS 1428.1-2009 & PART F2.4 OF THE BCA)

- WATER TAPS TO HAVE LEVER HANDLES WITH A CLEARANCE OF 50mm FROM ADJACENT SURFACES.
- HOT & COLD WATER TO BE DELIVERED THROUGH 1 SPOUT.
- TOILET SEAT TO BE A FULL ROUND TYPE, WITH A LOAD RATING OF 150kg AND A LUMINANCE CONTRAST OF 30% WITH BACKGROUND.
- BACKREST TO BE PROVIDED AS PER DETAILS
- FLUSHING CONTROLS ZONE AS PER SECTION 15.2.5 OF AS 1428.1-2009
- TOILET PAPER DISPENSER ZONE AS PER SECTION 15.2.6 OF AS 1428.1-2009
- GRABRAILS TO BE BETWEEN 30mm & 40mm DIAMETER WITH A CLEARANCE OF BETWEEN 50mm & 60mm FROM ANY SURFACE.
- DOORS TO BE PROVIDED WITH AN IN USE INDICATOR AND SHALL BE OPENED FROM THE OUTSIDE

ENERGY EFFICIENCY NOTES:


MECHANICAL VENTILATION AND AIR-CONDITIONING SYSTEM INSTALLED TO PROVIDE VENTILATION IN ACCORDANCE WITH BCA VOLUME 1 ARE TO BE COMPLIANT WITH AS 1668.2 & AS/NZS 3666.1. MECHANICAL VENTILATION AND AIR-CONDITIONING BY OWNER

MECHANICAL VENTILATION AND AIR-CONDITIONING SYSTEM INSTALLED TO PROVIDE VENTILATION IN ACCORDANCE WITH BCA VOLUME 1 ARE TO BE COMPLIANT WITH AS 1668.2 & AS/NZS 3666.1


AIR-CONDITIONING/VENTILATION SYSTEMS AND ARTIFICIAL LIGHTING TO BE DESIGNED AND INSTALLED IN ACCORDANCE WITH PARTS J.5 & J.6 OF THE BCA VOLUME 1 REQUIREMENTS FOR ENERGY EFFICIENCY

ALL HOT WATER SUPPLY SYSTEMS ARE REQUIRED TO BE INSTALLED IN ACCORDANCE WITH SECTION 8 OF AS 3500.4


OPERATION OF LATCH OF ALL EXIT DOORS TO COMPLY WITH CLAUSE D2.21 OF THE BCA.




SERVICES LEGEND	
	SUB MAINS CABLE (30AMPS)
	24 POLE SUB BOARD
	MAIN BOARD (POWER)
	M.D.F. BOARD (TELECOM)
	I.D.F. BOARD (TELEPHONE)
	36m FIRE HOSE REEL
	TEMPORARY WATER-PROOF DOUBLE GPO
	WATER TAP
	1 x 9kg DCP FIRE EXTINGUISHER TO BE INSTALLED IN OFFICE
	1 x 9kg DCP FIRE EXTINGUISHER TO BE INSTALLED IN WAREHOUSE




INTERNAL WALL LINING SCALE 1:10



BOUNDARY PANEL JOINT DETAIL SCALE 1:10



DOWNPIPE JOINER DETAIL SCALE 1:20



LOCATION OF TACTILE EXIT SIGNS SCALE 1:50

BRAILLE AND TACTILE SIGNAGE COMPLYING WITH SPECIFICATION D3.6 MUST IDENTIFY EACH DOOR REQUIRED BY E4.5 TO BE PROVIDED WITH AN EXIT SIGN AND STATE "EXIT" AND "LEVEL" FOLLOWED BY THE FLOOR NUMBER.

LOCATION OF BRAILLE AND TACTILE SIGNS SIGNS INCLUDING SYMBOLS, NUMBERING AND LETTERING MUST BE DESIGNED AND INSTALLED AS FOLLOWS:

SIGNS MUST BE LOCATED NOT LESS THAN 1200mm AND NOT HIGHER THAN 1600mm ABOVE THE FLOOR OR GROUND SURFACE. SIGNS WITH SINGLE LINES OF CHARACTERS MUST HAVE THE LINE OF TACTILE CHARACTERS NOT LESS THAN 1250mm AND NOT HIGHER THAN 1350mm ABOVE THE FLOOR OR GROUND SURFACE. SIGNS IDENTIFYING ROOMS CONTAINING FEATURES OR FACILITIES LISTED IN D3.6 MUST BE LOCATED ON THE WALL ON THE LATCH SIDE OF THE DOOR WITH THE LEADING EDGE OF THE SIGN LOCATED BETWEEN 50mm AND 300mm FROM THE ARCHITRAVE IN THE EVENT OF INSUFFICIENT LATCH SIDE DIMENSION, A SIGN MAY BE PLACED ON THE NON-LATCH SIDE OF THE DOOR WHERE (i) AND (ii) IS NOT POSSIBLE. THE SIGN MAY BE PLACED ON THE DOOR ITSELF. SIGNS IDENTIFYING PATHS OF TRAVEL MUST BE PLACED SO THEY ARE LOCATED DIRECTLY AHEAD IN THE DIRECTION OF TRAVEL. WHERE ONE WALL CONTINUES IN THE DIRECTION OF TRAVEL AND THE OTHER FORMS A CORNER, THE SIGN MUST BE PLACED ON THE CONTINUING WALL.

NOTE: ALL ELECTRICAL WORKS SHOWN ON ELECTRICAL PLAN, SEE E01

1	09/07/20	MWS	amenities and services adjusted
0	24/06/20	MWS	ISSUE FOR CONSTRUCTION
REV.	DATE	I.N.	DESCRIPTION



OUR BUSINESS IS BUILDING YOURS

41 Cedric Street, STIRLING
Western Australia 6200
t. 08 9209 1800 e. admin@vespoli.com.au
f. 08 9209 1899 w. www.vespoli.com.au
ACN 113 413 077 ABN 65 545 929 538

© COPYRIGHT
THIS DESIGN AND / OR DRAWING IS CONFIDENTIAL AND SHALL REMAIN THE PROPERTY OF VESPOLI CONSTRUCTIONS. IT MUST NOT BE REPRODUCED, COPIED OR ALTERED WITHOUT THE EXPRESSED APPROVAL OF VESPOLI CONSTRUCTIONS.

CONTRACTORS SHALL CHECK ALL DIMENSIONS AND CONDITIONS ON SITE PRIOR TO COMMENCING FABRICATION OR CONSTRUCTION. ANY DISCREPANCIES TO BE BROUGHT TO THE SUPERVISORS ATTENTION.
DO NOT SCALE FROM DRAWINGS.
THE DESIGNER RESERVES THE RIGHT TO ALTER DIMENSIONS ON SITE TO SUIT CONSTRUCTION, ENGINEERING OR SITE CONDITIONS.
UNLESS OTHERWISE NOTED, RETAINING WALLS, DEMOLITION SEWER PILING, SUBSOL DRAINS, BLASTING OR OTHER SITE WORKS ARE ALL AT OWNERS EXPENSE

PROPOSED AUTO SERVICE CENTRE DEVELOPMENT
LOT311 NICHE PARADE WANGARRA

DRAWING TITLE:
FLOOR PLAN & DETAILS

DRAWING No. **A03**
JOB No. **A19015**

drawn MWS date 05.03.20 PAGE No. 3
checked AS SHOWN REV No. 1

ISSUED FOR CONSTRUCTION